S.No.	Component	Description	New Qty.	Total Qty.
		Intel Xeon Gold 5418Y 2G, 24C/48T, 16GT/s, 45M Cache, Turbo, HT		
		(185W)	2	
		64GB RDIMM, 4800MT/s Dual Rank	8	
		480GB SSD SATA RI 6Gbps 512 2.5in, 1 DWPD	2	2
		Dual Port 10GbE BASE-T Adapter	2	_
		Quad Port 1GbE BASE-T Adapter	1	
		Dual Port FC16 Fibre Channel HBA	2	
1	Server	5yrs 4hr 24x7 Onsite Support	1	
1	Servei	Dual Controler All Flash SAN	1	
		2 x 6-core 1.7 GHz or higher	1	
		Per Node Cache 64GB or higher	1	
		16GBPS FC Ports	8	
		10G BASE-T (Copper)	4	
		1.92TB SSD/3.84 TB SSD(NVMe) OR Higher Total Usable Space		
		30TB or higher with Raid 6 ,minimum 8 Drives to be supplied	1	_
		IOPS :2 Lakhs or more with 8K block size with 60:40 Read ,Write ratio	1	
		Expandable tiill 250TB		
		De Dupp/Snapshot/cloning	1	
		5yrs 4hr 24x7 Onsite Support	1	
2	Storage	Hardware install +Configuration	1	
		32 Port SAN Switch	1	1
		16*16 Gbps FC Ports,16*5m fiber cables and redundant power	_	
		supply	1	
3	SAN Switch	5yrs 4hr 24x7 Onsite Support	1	
		Microsoft Windows Server 2022 (Datacenter Edition) (16 Core		
4	OS	Pack)	3	2 lots
5	Implementation	One Time	1	1
		Storage Hardware & software should have life & support for 7		
		Years from the date of installation & commissionin		
Total				_

Scope of Work				
Delivery of Hardware and OS license and registration				
Registration of material supplied in respective portal				
Warranty to be started after delivery				
Installation of Hardware and software provided				
Operating System Installation				
Microsoft Hyper-V Installation				
Virtual Machine Creation minimum 6 including Networking and				
storage Configuration and allocation				
Operating System Installation on VMs and Security Hardening				
Document the server and virtualization environment				
configuration, including IP addresses, VM configurations, and				
security policies. Provide training to administrators and users on				
using and managing the virtualized environment effectively.				
Storage Hardware & software should have life & support for 7				
Years from the date of installation & commissioning				