



BSES Yamuna Power Limited

<b>CORRIGENDUM 2</b>		Response to the pre-bid queries and change in tender conditions accordingly		
<b>Date:</b>		03.11.2021		
<b>BYPL NIT NO:</b>		CMC/BY/21-22/RS/SvS/AS/28 DT: 14.10.2021		
<b>Work:</b>		Award of rate contract for carrying out meter installation (MMG) work in 14 divisions of BYPL		
<b>Change in Price format</b>				
<b>Sl.No</b>	<b>Clause Reference</b>	<b>Description</b>	<b>Bidders Query</b>	<b>BYPL Response</b>
1	Price format, Section VI, page 57	Due to varriation in Estimated quantity , price format is changed	-	Please submit the Financial bid in revised price format attached .

Section VI

Part A(1). PRICE FORMAT FOR MMG (including Transportation in item rate) .....

SR	Service Code	Description	Uom	Annual EstimatedQuantity	Rate (Rs.) excluding GST	Total
A	B	C	D		F	G
1	<b>Installation/Replacement of any type single phase meter</b>	Installation/Reinstallation/Replacement(including Load change)/Reconnection (with meter installation) for any type of Single Phase Meter including Smart Meter (including loop connection of cable length up to 3 meters) on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	150000		
2	<b>Installation/Replacement of any type Three phase meter</b>	Installation/Reinstallation/Replacement(including Load change)/Reconnection (with meter installation) for any type of Three Phase Meter including Smart Meter (including loop connection of cable length up to 3 meters) on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	10		
3	<b>Removal of Single Phase Meter with Service line</b>	Removal of Single Phase meter with box from the consumer site with service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	8800		
4	<b>Removal of Single Phase Meter without Service line</b>	Removal of Single Phase meter with box from the consumer site without service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	7700		

5	<b>Removal of Three Phase Meter with Service Line</b>	Removal of Three Phase meter with box from the consumer site with service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	10		
6	<b>Removal of Three Phase Meter without Service Line</b>	Removal of Three Phase meter with box from the consumer site without service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	10		
7	<b>Shift of any type of Single Phase Meter</b>	Shifting of any type of Single Phase meter with/without box, with/ without service line including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, sealing of Meters / Meter Box / Bus Bar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter shifting Filling up of MCRs, lab format, Quality Formats, timely submission of MCRs at MMG Circle office and any other work required to complete the job.	EA	6800		
8	<b>Shift of any type of Three Phase Meter</b>	Shifting of any type of Three Phase meter with/without box, with/ without service line including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, sealing of Meters / Meter Box / Bus Bar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter shifting Filling up of MCRs, lab format, Quality Formats, timely submission of MCRs at MMG Circle office and any other work required to complete the job.	EA	10		
9	<b>Reconnection single phase without meter</b>	Reconnection without meter installation for single phase connection by laying any type, size & length of service line on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Taking Photographs (03 photo/case) of meter reconnection, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	1000		

10	<b>Reconnection Three phase without meter</b>	Reconnection without meter installation for Three phase connection by laying any type, size & length of service line on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Taking Photographs (03 photo/case) of meter reconnection, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	10		
11	<b>Installation/ Replacement O/H S-Line size 2x10 &amp; 2x25, length 4-30 meters</b>	Installation / Replacement & fixing of O/H XLPE service line cable size 2x10 & 2x25 sq. mm for lengths 4 to 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	70000		
12	<b>Installation/ Replacement O/H S-Line size 2x10 &amp; 2x25, length more than 30 meters</b>	Installation / Replacement & fixing of O/H XLPE service line cable size 2x10 & 2x25 sq. mm for lengths over 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	55000		
13	<b>Installation/ Replacement O/H S-Line size 4x25 &amp; 4x50, length 4-30 meters</b>	Installation / Replacement & fixing of O/H XLPE service line cable size 4x25 & 4x50, sq. mm for lengths 4 to 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	230		
14	<b>Installation/ Replacement O/H S-Line size 4x25 &amp; 4x50, length more than 30 meters</b>	Installation / Replacement & fixing of O/H XLPE service line cable size 4x25 & 4x50, sq. mm for lengths over 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	150		
15	<b>Installation/ Replacement O/H S-Line size 3.5x95 to 3.5x300, length 4-30 meters</b>	Installation / Replacement & fixing of O/H XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths 4 to 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	10		

16	<b>Installation/ Replacement O/H S-Line size 3.5x95 to 3.5x300, length more than 30 meters</b>	Installation / Replacement & fixing of O/H XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths over 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	10		
17	<b>Installation/ Replacement U/G S-Line size 2x10 &amp; 2x25, length 4- 30 meters</b>	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 2x10 & 2x25 sq. mm for lengths of 4 to 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	1000		
18	<b>Installation/ Replacement U/G S-Line size 2x10 &amp; 2x25, length more than 30 meters</b>	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 2x10 & 2x25 sq. mm for lengths over 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	100		
19	<b>Installation/ Replacement U/G S-Line size 4x25 &amp; 4x50, length 4- 30 meters</b>	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 4x25 & 4x50 sq. mm for lengths of 4 to 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	150		
20	<b>Installation/ Replacement U/G S-Line size 4x25 &amp; 4x50, length more than 30 meters</b>	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 4x25 & 4x50 sq. mm for lengths over 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	130		
21	<b>Installation/ Replacement U/G S-Line size 3.5x95 to 3.5x300, length 4-30 meters</b>	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths of 4 to 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	10		

22	<b>Installation/ Replacement U/G S-Line size 3.5x95 to 3.5x300, length more than 30 meters</b>	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths over 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	10		
23	<b>Installation/Replacement of 1 Ph/ 3 Ph Busbar Chamber upto 4 Con</b>	Installation/Replacement of Single Phase / Three Phase Bus Bar Chamber up to 4 connections including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	900		
24	<b>Installation/Replacement of 3 Ph Busbar Chamber upto 8 Con</b>	Installation/Replacement of Three Phase Bus Bar Chamber up to 8 connections including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	700		
25	<b>Removal of Service Line Single Phase Meter</b>	Removal of service line of any type, Size and length for Single Phase meters including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	150		
26	<b>Removal of Service Line Three Phase Meter</b>	Removal of service line of any type, Size and length for Three Phase meters including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	10		
27	<b>Disconnection of Consumer</b>	Disconnection of consumer for all type of Single Phase, Three Phase & LTCT connection by disconnecting the cable of any type, size & length from the pole/feeder pillar including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	700		
28	<b>Reconnection of Consumer</b>	Reconnection of consumer for all type of Single Phase, Three Phase & LTCT connection by reconnecting the cable of any type, size & length from the pole/feeder pillar including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	500		
29	<b>Reseal of Energy Meter/Meter Box/Busbar</b>	Resealing of any type of single phase/ three phase/LTCT Meter/Meter Box/ Busbar including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, Filling up of MCRs and any other work required to complete the job	EA	36000		

30	<b>Fixing/ Replacement of data cord in meter box</b>	Fixing/ Replacement of data cord/communication cable in any type of meters/meter box including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, sealing of meters / meter Box, filling up of MCRs, timely submission of MCRs at MMG circle office and any other work required to complete the job	EA	3200		
31	<b>Survey Charge</b>	Consumer site survey against the exception service order generated through MRDC remarks including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, filling up of site reports, timely submission of reports at MMG circle office and any other work required to complete the job.	EA	7500		
32	<b>Service line Anchor at consumer Side</b>	Fixing/Installation of MS/GI Bracket Angle/ MS Bracket (L-Type) with fastener, Service Clamp Anchor at consumer end for anchoring the of service cable of all Size, including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, and any other work required to complete the job.	EA	44000		
33	<b>Service line Anchor at Pole Side</b>	Fixing/Installation of GI Slotted angle with D-Clamp/ GI two line cross arm at Pole end and Service Clamp Anchor for anchoring the service cable of all Size, including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, and any other work required to complete the job.	EA	5000		
34	<b>Fixing of Piercing Connector</b>	Fixing/Installation of Piercing Connection up to 300mm <sup>2</sup> size to energize the service connection of consumers including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, and any other work required to complete the job.	EA	14000		
35	<b>Single Phase Meter replacement with Enforcement team</b>	Installation/Replacement of any type of Single Phase Meter on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to Enforcement Team/ assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	250		
36	<b>Three Phase Meter replacement with Enforcement team</b>	Installation/Replacement of any type of Three Phase Meter on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to Enforcement Team/ assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job	EA	10		

37	<b>Videography of Old Meter in Lab Bag</b>	Making of video of old removed meter packing process in the bag, sealing of bag in consumer presence for testing of meters in Testing Lab and submitting of video CA/ Order No. Wise to BSES Circle office in soft copy.	EA	80000		
38	<b>Supply &amp; Installation of Iron Angle Bracket for Meter installation</b>	Fabrication, Supply & Installation of Iron Angle Bracket for meter installation outside premises using MS steel (as per drawing specification provided by BSES) including all material , consumables i.e. providing red oxide primer and one coat of aluminium paint , nuts , bolts and washers , size (30*30*3 MM), supply and erection of 5mm Bakelite sheet , size (300*300*3 ) mm including all material and consumables , installation of fabricated frame on wall including all material & consumables e.g fastner , Drill M/C “	EA	1500		
39	<b>Fixing/ Replacement of SIM/ AMR/ Data Cord in all type of meters.</b>	Fixing/ Replacement of SIM/ AMR/ Data cord/ Data Cable/ Communication cable in GCC/ Pre-Paid/ MLCC/ LTCT Meter/ HT Meters/ Smart Meters/ Meter box to maintain communication with HES including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/ busbar, display/freedom unit, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	50		
40	<b>Installation/ Replacement of IGMS Box</b>	Installation/Replacement of IGMS meter box including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, Inserting the SIM in DCU, sealing of IGMS meter Box, filling up of MCRs, timely submission of MCRs at MMG circle office and any other work required to complete the job	EA	100		
41	<b>Replacement of DCU</b>	Replacement of DCU in IGMS meter box including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, Inserting the SIM in DCU, sealing of IGMS meter Box, filling up of MCRs, timely submission of MCRs at MMG circle office and any other work required to complete the job.	EA	100		
42	<b>Fixing/ Replacement of SIM/ Data Cable</b>	Fixing/ Replacement of SIM/ Data Cable/ Communication cable in IGMS Meters/ Meter box to maintain communication with HES including all the activities related to installation like, sealing of meter/box/ bus bar, display/freedom unit, filling up of MCRs, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	100		
43	<b>Installation/ Replacement of burnt/fault IGMS meters along with display unit and vice versa</b>	Installation/ Replacement of IGMS meters along with display unit and vice versa including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, fastener, any other way including all the activities related to installation like, sealing of meter/box/ bus bar, filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	100		
44	<b>Disconnection /Connection of LT cable for providing supply to IGMS unit</b>	Disconnection /Connection of LT cable for providing supply to IGMS unit including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, any other way including all the activities related to installation. and Any other work required to complete the job.	EA	100		



45	<b>Providing support to Project Manager and RCM Team</b>	Providing support to Project Manager and RCM Team in conjunction with O&M Sub Divisional In charge, AM(PS) & IT team.	EA	100		
					a) Total	0
					<a href="#">b) GST@18%</a>	0
					Grand Total(a+b)	0

**Part B(1) Price format for MLCC /KCC/GCC/Prepaid /CT meter (including Transportation in item rate) .....**

Sr No	Short Text	Description	UOM	Annual Estimated Quantity	RATE(Excluding GST)	Total
A	B	C	D	E	F	G
1	Installation/Replacement of any type of Single Phase Meter	Installation/Reinstallation/Replacement(including Load change)/Reconnection (with meter installation) for any type of Single Phase Meter including Smart Meter (including loop connection of cable length up to 3 meters) on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	1300		
2	Installation/Replacement of any type of Three Phase Meter	Installation/Reinstallation/Replacement(including Load change)/Reconnection (with meter installation) for any type of Three Phase Meter including Smart Meter (including loop connection of cable length up to 3 meters) on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	5500		
3	Installation/Replacement of any type of Three Phase LTCT Meter with LTCT Box	Installation/Reinstallation/Replacement including smart meter (including Load change)/Reconnection (with meter installation) for any type of Three Phase LTCT Meter including LTCT box (including loop connection of cable length up to 3 meters) in the Box/Panel/any other way including all the activities related to installation like, Transportation of meter/ cable/ material/ manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned	EA	200		

		BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.				
4	Installation/Replacement of any type of Three Phase LTCT Meter without Box (Only Meter)	Installation/Reinstallation/Replacement(including Load change)/Reconnection (with meter installation) for any type of Three Phase LTCT Meter without LTCT box in the Box/Panel/any other way including all the activities related to installation like, Transportation of meter/ cable/ material/ manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	36		
5	Installation/Replacement of any type of Three Phase LTCT box without meter (Only box )	Installation/Reinstallation/Replacement(including Load change)/Reconnection for any type of Three Phase LTCT box without LTCT meter in the Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	36		
6	Removal of Single Phase Meter with Service Line	Removal of Single Phase meter with box from the consumer site with service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	280		
7	Removal of Single Phase Meter without Service Line	Removal of Single Phase meter with box from the consumer site without service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	180		

8	Removal of Three Phase Meter with Service Line	Removal of Three Phase meter with box from the consumer site with service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	1500		
9	Removal of Three Phase Meter without Service Line	Removal of Three Phase meter with box from the consumer site without service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	350		
10	Removal of Three Phase LTCT Meter with Service Line	Removal of Three Phase LTCT meter with box from the consumer site with service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	60		
11	Removal of Three Phase LTCT Meter without Service Line	Removal of Three Phase LTCT meter with box from the consumer site without service line including return of removed old meter with/without gunny bag, material & scrap to assigned BSES store, transportation of material/manpower from BSES to division store and division store to site & vice-versa, filling up of MCRs, Lab Formats, timely submission of MCRs and any other work required to complete the job	EA	12		
12	Shift of any type of Single Phase Meter	Shifting of any type of Single Phase meter with/without box, with/ without service line including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, sealing of Meters / Meter Box / Bus Bar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter shifting Filling up of MCRs, lab format,Quality Formats, timely submission of MCRs at MMG Circle office and any other work required to complete the job.	EA	72		
13	Shift of any type of Three Phase Meter	Shifting of any type of Three Phase meter with/without box, with/ without service line including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, sealing of Meters / Meter Box / Bus Bar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter shifting Filling up of MCRs, lab format,Quality Formats, timely submission of MCRs at MMG Circle office and any other work required to complete the job.	EA	500		

14	Shift of any type of Three Phase LTCT Meter with Box	Shifting of any type of Three Phase LTCT meter with box, with/ without service line including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, sealing of Meters / Meter Box / Bus Bar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & old meter with/without gunny bags to assigned BSES stores, Taking Photographs (03 photo/case) of meter shifting Filling up of MCRs, lab format,Quality Formats, timely submission of MCRs at MMG Circle office and any other work required to complete the job.	EA	36		
15	Reconnection single phase without meter	Reconnection without meter installation for single phase connection by laying any type, size & length of service line on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Taking Photographs (03 photo/case) of meter reconnection, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	300		
16	Reconnection Three phase without meter	Reconnection without meter installation for Three phase connection by laying any type, size & length of service line on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Taking Photographs (03 photo/case) of meter reconnection, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	200		
17	Reconnection without Three phase LTCT meter	Reconnection without meter installation for Three phase LTCT meter connection by laying any type, size & length of service in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Taking Photographs (03 photo/case) of meter reconnection, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	50		
18	Installation/ Replacement O/H S-Line size 2x10 & 2x25, length 4-30 meters	Installation / Replacement & fixing of O/H XLPE service line cable size 2x10 & 2x25 sq. mm for lengths 4 to 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to	EA	500		

		assigned BSES store and any other work required to complete the job.				
19	Installation/ Replacement O/H S-Line size 2x10 & 2x25, length more than 30 meters	Installation / Replacement & fixing of O/H XLPE service line cable size 2x10 & 2x25 sq. mm for lengths over 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	300		
20	Installation/ Replacement O/H S-Line size 4x25 & 4x50, length 4-30 meters	Installation / Replacement & fixing of O/H XLPE service line cable size 4x25 & 4x50, sq. mm for lengths 4 to 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	3000		
21	Installation/ Replacement O/H S-Line size 4x25 & 4x50, length more than 30 meters	Installation / Replacement & fixing of O/H XLPE service line cable size 4x25 & 4x50, sq. mm for lengths over 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	2500		
22	Installation/ Replacement O/H S-Line size 3.5x95 to 3.5x300, length 4-30 meters	Installation / Replacement & fixing of O/H XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths 4 to 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	30		
23	Installation/ Replacement O/H S-Line size 3.5x95 to 3.5x300, length more than 30 meters	Installation / Replacement & fixing of O/H XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths over 30 Meters for energisation of service connection at consumer premises including supply and fixing of steel saddles clamp, fasteners for support of cable, transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	400		

24	Installation/ Replacement U/G S-Line size 2x10 & 2x25, length 4-30 meters	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 2x10 & 2x25 sq. mm for lengths of 4 to 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	12		
25	Installation/ Replacement U/G S-Line size 2x10 & 2x25, length more than 30 meters	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 2x10 & 2x25 sq. mm for lengths over 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	24		
26	Installation/ Replacement U/G S-Line size 4x25 & 4x50, length 4-30 meters	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 4x25 & 4x50 sq. mm for lengths of 4 to 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	400		
27	Installation/ Replacement U/G S-Line size 4x25 & 4x50, length more than 30 meters	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 4x25 & 4x50 sq. mm for lengths over 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	400		
28	Installation/ Replacement U/G S-Line size 3.5x95 to 3.5x300, length 4-30 meters	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths of 4 to 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	60		

29	Installation/Replacement U/G S-Line size 3.5x95 to 3.5x300, length more than 30 meters	Laying (Installation /Replacement) & fixing of U/G XLPE service line cable size 3.5x95 to 3.5x300 sq. mm for lengths over 30 meters including excavation of trench, backfilling, docketing with bricks & sand, making of connections as required at site at consumer premises, inclusive of clamps & all other allied material (except cable), transportation of cable/material/manpower from BSES store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	M	1000		
30	Installation/Replacement of 1 Ph/ 3 Ph Busbar Chamber upto 4 Con	Installation/Replacement of Single Phase / Three Phase Bus Bar Chamber up to 4 connections including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	10		
31	Installation/Replacement of 3 Ph Busbar Chamber upto 8 Con	Installation/Replacement of Three Phase Bus Bar Chamber up to 8 connections including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store and any other work required to complete the job.	EA	10		
32	Removal of Service Line Single Phase Meter	Removal of service line of any type, Size and length for Single Phase meters including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	40		
33	Removal of Service Line Three Phase Meter	Removal of service line of any type, Size and length for Three Phase meters including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	60		
34	Removal of Service Line Three Phase LTCT Meter	Removal of service line of any type, Size and length for Three Phase LTCT meters including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	12		
35	Disconnection of Consumer	Disconnection of consumer for all type of Single Phase, Three Phase & LTCT connection by disconnecting the cable of any type, size & length from the pole/feeder pillar including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	10		
36	Reconnection of Consumer	Reconnection of consumer for all type of Single Phase, Three Phase & LTCT connection by reconnecting the cable of any type, size & length from the pole/feeder pillar including transportation of cable/material/manpower from BSES Store to division store and division store to site & vice-versa, return of scrap to assigned BSES store, and any other work required to complete the job.	EA	50		

37	Reseal of Energy Meter/Meter Box/Busbar	Resealing of any type of single phase/ three phase/LTCT Meter/Meter Box/ Busbar including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, Filling up of MCRs and any other work required to complete the job	EA	3500		
38	Fixing/ Replacement of data cord in meter box	Fixing/ Replacement of Data cord/ Data Cable/ Communication cable in any type of meters/meter box including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, sealing of meters / meter Box, filling up of MCRs, timely submission of MCRs at MMG circle office and any other work required to complete the job	EA	100		
39	Survey Charge	Consumer site survey against the exception service order generated through MRDC remarks including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, filling up of site reports, timely submission of reports at MMG circle office and any other work required to complete the job.	EA	250		
40	Service line Anchor at consumer Side	Fixing/Installation of MS/GI Bracket Angle/ MS Bracket (L-Type) with fastener, Service Clamp Anchor at consumer end for anchoring the of service cable of all Size, including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, and any other work required to complete the job.	EA	800		
41	Service line Anchor at Pole Side	Fixing/Installation of GI Slotted angle with D-Clamp/ GI two line cross arm at Pole end and Service Clamp Anchor for anchoring the service cable of all Size, including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, and any other work required to complete the job.	EA	150		
42	Fixing of Piercing Connector	Fixing/Installation of Piercing Connection up to 300mm <sup>2</sup> size to energize the service connection of consumers including transportation of material / manpower from BSES store to division store and division store to site & vice-versa, and any other work required to complete the job.	EA	3600		
43	Single Phase Meter replacement with Enforcement team	Installation/Replacement of any type of Single Phase Meter on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & return of old meter with/without gunny bags to Enforcement Team/ assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	10		



44	Three Phase Meter replacement with Enforcement team	Installation/Replacement of any type of Three Phase Meter on base plate/Meter Box/Prefitted in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & return of old meter with/without gunny bags to Enforcement Team/ assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	50		
45	Three Phase LTCT Meter replacement with Enforcement team	Installation/Replacement of any type of Three Phase LTCT Meter with LTCT box in Box/Panel/any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & return of old meter with/without gunny bags to Enforcement Team/ assigned BSES stores, Taking Photographs (03 photo/case) of meter installation, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	10		
46	Videography of Old Meter in Lab Bag	Making of video of old removed meter packing process in the bag, sealing of bag in consumer presence for testing of meters in Testing Lab and submitting of video CA/ Order No. Wise to BSES Circle office in soft copy.	EA	10		
47	Installation/ Replacement of Display Unit	Installation/ Replacement of Display/ Freedom unit for any type of Pre-paid Meters including laying of communication wire, supply & fixing of RJ11 connector, fastener, any other way including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/ busbar, display/freedom unit, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	10		
48	Fixing/ Replacement of SIM/ AMR/ Data Cord in all type of meters.	Fixing/ Replacement of SIM/ AMR/ Data cord/ Data Cable/ Communication cable in GCC/ Pre-Paid/ MLCC/ LTCT Meter/ HT Meters/ Smart Meters/ Meter box to maintain communication with HES including all the activities related to installation like, Transportation of meter/cable/material/manpower from BSES Store to division store and division store to site & vice-versa, Sealing of meter/box/ busbar, display/freedom unit, Filling up of MCRs, Lab Formats & Quality Reports, Timely submission of MCRs at MMG circle office and Any other work required to complete the job.	EA	1200		

49	Installation/ Replacement of Metering Cubical	Installation/ Replacement of any type/ rating of metering cubical for HT consumers including all the activity related to installation/ replacement of cubical like High Voltage Test (High-Pot-Equipment by Contractor), dismantling of cubical, disconnection/ reconnection of cubical, supply of nut bolt, welding as per site requirement, Interconnection of cubical, Transportation of metering cubical/ cable/material/manpower from BSES Store to division store and division store to site & vice-versa, manpower & crane for loading/ unloading of cubical at store/site/BSES office, Sealing of metering cubical/box/busbar, Earthing at both ends of supply cable ( Including Earthing material supply by contractor ), Return of scrap, material & return of old metering cubical, Taking Photographs (03 photo/case) of cubical installation, Timely submission of installation reports at BSES circle office and Any other work required to complete the job of cubical installation/ replacement including supply of channel .	EA	15		
50	3003167	E3010228-Prov/Fix/Embos,Lead Tag	EA	100		
51	3005581	C10414-Supply of HDPE-110mm	M	100		
52	3005494	C10414-CrosRdTr Less m/c-110/140-W/OHDPE	M	100		
53	3007917	C10414-CrosRdTr by Trct -110/140-W/OHDPE	M	100		
54	3005499	C10414-CrosRdTrLes Pneu110/140 W/OHDPE	M	100		
55	Supply & Installation of Iron Angle Bracket for Meter installation	Fabrication, Supply & Installation of Iron Angle Bracket for meter installation outside premises using MS steel (as per drawing specification provided by BSES) including all material , consumables i.e. providing red oxide primer and one coat of aluminium paint , nuts , bolts and washers , size (30*30*3 MM), supply and erection of 5mm Bakelite sheet , size (300*300*3 ) mm including all material and consumables , installation of fabricated frame on wall including all material & consumables e.g fastner , Drill M/C "	EA	10		
56	HT Meter Testing	Providing one lineman and Vehicle for HT meter testing.	EA	888		
57	Energize/Connection of Wi-Fi connections without meter	Energize/Connection of Wi-Fi connections by laying of service cable of 2*10 sqmm size upto length of 7 meter from the Pole /Feeder pillar without meter installation	EA	100		
					a) Total	
					<a href="#">b) GST@18%</a>	
					Grand Total(a+b)	